

डा0 राम मनोहर लोहिया राष्ट्रीय विधि विश्वविद्यालय Dr. Ram Manohar Lohiya National Law University

No. 7/9-22 NLULko/Admin/M-49/2020(22456) Date: 20 May, 2022

Quotation Notice

Item wise rates of sealed Quotations are invited for the following work of supply and fixing of Flush Door in Boys Hostel (UG) with an Estimated cost of Rs. 91,746.00 B.O.Q. of work as per Annexure-1. The quotations shall be received by speed post and by hand addressed to, "Assistant Registrar (A.S.) RMLNLU Lucknow-226025" in the Universityup to 3:00P.M. till 28-05-2022.

The quotations are available on the website of the University/main gate of the University only and may be downloaded from rmlnlu.ac.in Conditions:-

- 1. The rates quoted should include the rates for all materials, labour, T&P, cartage, taxes, etc. required for proper completion of work.
- 2. Work should be carried out as per all edition of C.P.W.D. UPPWD, specificatins.
- 3. All material required for completion of work shall conform to latest ISI/ C.P.W.D. UPPWD, specificatins.
- 4. Payment shall be released after completion of work to the satisfaction of Engineer-incharge.
- 5. Time of completion shall be 15 Days.
- 6. Income Tax/GST tax shall be deducted as per rule of Government of India/State Government.
- 7. Rates quoted shall be valid at least for three months from the date of opening of the quotations.
- 8. University has the right to reject and one or all quotations without assigning any reason

Assistant Registrar

Copy To:-

1- Registrar, Dr. RML National Law University, Lucnow.

2- Finance Officer, Dr. RML National Law University, Lucnow.

3 -In-charge website with a request to upload it on the website of the University.

Assistant Registrar

		Name of work - door worl		TOSTEE.		
		Bill Of Quant	tity			
	Reference		0.1		Rate	Amoun
S.N.	No.	Description of work	Qty	unit	Nate	Allioun
1		Provinding isi marked flush door				
		shutters conforming to is 2202				
		non decorative type,core of				
		block board constrution with				
		fram of 1st class hard wood and				
		well matched commerical 3ply				
		veneering with vertical grains.				
	DSR-		47.04			
	9.21		17.01	sqm		
2						
		Provinding wood work infromes				
		of door window clerestory				
		window and other frames				
		wrought framed fixing in				
	5.55	position with hold fast lugs or				
	DSR-	with fasteners of required dia	0.322	sum.		
	9.1.1	and length.	0.522	Cum		
3						
		Fixing chowkhats in existng				
		opening inluding embedding				
		chowkhats in floors or walls				
		cutting masonry for holdfasts				
		embedding hold fasts in cement				
		concrete blocks of size				
		15*10*10 cm with cement				
		concrete 1;3;6 painting two				
		coats of approved wood				
		preservative to side of				
		chowkhats and making good				
		the damages to walls and floors				
		as required complete. Door				
	DAR 14.2.1	chowkhats	0	nos		
	D, 111 1 1.2.1	CHOWKHULS	9	nos		

gst @18% Net amount