



डा० राम मनोहर लोहिया राष्ट्रीय विधि विश्वविद्यालय Dr. Ram Manohar Lohiya National Law University

धर्म सरथापनार्थीय

No: 177-24 NLULko/Admin/S-38/2016(1235)
Date: 14 February, 2024

Quotation Notice

Item wise rates of sealed Quotations are invited for the following work of Laying of Sewer Line and Construction of Sewer Chamber Estimated cost of Rs. 85,195 B.O.Q. of work as per Annexure-1. The quotations shall be received by speed post and by hand addressed to, "Joint Registrar RMLNLU Lucknow-226012" in the University up to 3:00P.M. till 19-02-2024.

The quotations are available on the website of the University/main gate of the University only and may be downloaded from rmlnu.ac.in

Conditions:-

1. The rates quoted should include the rates for all materials, labour, T&P, cartage, taxes, etc. required for proper completion of work.
2. Work should be carried out as per all edition of C.P.W.D. UPPWD. specificatins.
3. All material required for completion of work shall conform to latest ISI/ C.P.W.D. UPPWD. specificatins.
4. Payment shall be released after completion of work to the satisfaction of Engineer-in-charge.
5. Time of completion shall be 15 Days.
6. Income Tax/GST tax shall be deducted as per rule of Government of India/State Government .
7. Rates quoted shall be valid at least for three months from the date of opening of the quotations.
8. University has the right to reject and one or all quotations without assigning any reason

/
Joint Registrar

Copy To:-

1- Main Gate Notice Board.

2 In-charge website with a request to upload it on the website of the University.

Sanjay
Joint Registrar

annexuer-1

Name of work -Laying of sewer line and Construction of sewer chamber near ug
hostel back side

Bill Of Quantity

S.N.	Reference No.	Description of work	Qty	unit	Rate	Amount
1	19.7.1.1	Constructing brick masonry manhole in cement mortar 1:4 (1 cement : 4 coarse sand) with R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement: 3 coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design :				
		Inside size 90x80 cm and 45 cm deep including C.I. cover with frame (light duty) 455x610 mm internal dimensions, total weight of cover and frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg) :				
		With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	2	nos		
2	dsr 19.35	Providing and laying Non Pressure NP-3 class (Medium duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete				
	19.35.2	600 mm dia RCC pipes.	16	rm		
					total amount	
					Est@18%	
					Net amount	

neeraj