



# डा० राम मनोहर लोहिया राष्ट्रीय विधि विश्वविद्यालय Dr. Ram Manohar Lohiya National Law University

No. 2009-22 NLULko/Admin/M-50/2020(2457)  
Date: 9 November, 2022

## Quotation Notice

Item wise rates of sealed Quotations are invited for the following work of Railing, Plaster and Tiles work in PG Hostel. Estimated cost of Rs. 83566/- B.O.Q. of work as per Annexure-1. The quotations shall be received by speed post and by hand addressed to, "Registrar" RMLNLU Lucknow-226012" in the University up to 3:00P.M. till 16-11-2022.

The quotation notice are available on the website of the University/main gate of the University only and may be downloaded from rmlnlu.ac.in

### Conditions:-

1. The rates quoted should include the rates for all materials, labour, T&P, cartage, taxes, etc. required for proper completion of work.
2. Work should be carried out as per all edition of C.P.W.D. UPPWD, specificatins.
3. All material required for completion of work shall confirm to latest ISI/ C.P.W.D. UPPWD, specificatins.
4. Payment shall be released after completion of work to the satisfaction of Engineer-in-charge.
5. Time of completion shall be 7 Days.
6. Income Tax/GST tax shall be deducted as per rule of Government of India/State Government .
7. Rates quoted shall be valid at least for three months from the date of opening of the quotations.
8. University has the right to reject and one or all quotations without assigning any reason.
9. Tenderer should be mention the quotation Notice number and date along with proprietor's Name, Signature and Date.

(Anil Kumar Mishra)  
Registrar

### Copy To:-

- 1- Finance Officer, Dr. RML National Law University, Lucnow.
- 2- In-charge website with a request to upload it on the website of the University.
- 3- University Main Gate Copy(Display Board).

(Anil Kumar Mishra)  
Registrar

## Bill of quantity

| S.N. | Reference No. | Description of work  | Qty   | unit | Rate       | Amount |
|------|---------------|--|-------|------|------------|--------|
| 1    | SOR-21        | s/o hand rail and balustrade modular system passive ss 304 grade decorative railing system comprising of hand rail 50 mm and 1.5 mm thick and 3 no horizontal steel pipe of 19 mm dia and 1.5 mm thick of equal spacing with balustrade of ss pipe of 38 mm and 1.5 mm thick @1200mm c/c of passivated ss 304 grade and fix duly on the floor with specially design rivet expansion bolt and finish the surface food and covering with steel shoe with all visible stainless steel metal of 304 grade in strain finish height of railing is 900 mm as per details specification. |       |      |            |        |
|      |               | mess back side   | 9.14  | rm   |            |        |
| 2    | DSR-13.6.1    | 20 mm cement plaster of mix 1;6  |       |      |            |        |
|      |               |  | 26.54 | sqm  |            |        |
| 3    | DSR 11.40     | providing and laying rectified glazed ceramic floor antiskid tiles of size 300*300 mm or more of frist quality conforming to IS 15622 of approved make in all colours and shades laid on 20mm thick cement motar 1:4 ,jointing with grey cement slurry @ 3.3kg/sqm including grouting the joint with white cement and matching pigment etc. complete   |       |      |            |        |
|      |               |  | 11    | sqm  |            |        |
| 4    | DSR 11.41     | providing and laying vitrified floor tiles in different sizes with water abosorption less than 0.08% and conforming to IS 15622 of approved make in all colours and shades laid on 20mm thick cement motar 1:4 ,jointing with grey cement slurry @ 3.3kg/sqm including grouting the joint with white cement and matching pigment etc. complete   |       |      |            |        |
|      |               |  | 9.88  | Sqm  |            |        |
|      |               |  |       |      | AMOUNT     |        |
|      |               |  |       |      | GST@18%    |        |
|      |               |  |       |      | Net amount |        |

*neeey*  
*2/10/21*