



डा० राम मनोहर लोहिया राष्ट्रीय विधि विश्वविद्यालय
Dr. Ram Manohar Lohiya National Law University

No. ~~810-22~~ NLULko/AR/V-1(1)/2019(2309)

Date: 04 May 2022
JUNE

Quotation Notice

Item wise rates of sealed Quotations are invited for the following work of construction of Dias in Room No. G-19 of Lecture Hall Estimated cost of Rs. 60206/- B.O.Q. of work as per Annexure-1. The quotations shall be received by speed post and by hand addressed to, "Assistant Registrar (A.S.) RMLNLU Lucknow-226025" in the University up to 3:00P.M. till 10-06-2022.

The quotations are available on the website of the University/main gate of the University only and may be downloaded from rmlnlu.ac.in

Conditions:-

1. The rates quoted should include the rates for all materials, labour, T&P, cartage, taxes, etc. required for proper completion of work.
2. Work should be carried out as per all edition of C.P.W.D. UPPWD, specificatins.
3. All material required for completion of work shall conform to latest ISI/ C.P.W.D. UPPWD, specificatins.
4. Payment shall be released after completion of work to the satisfaction of Engineer-in-charge.
5. Time of completion shall be 15 Days.
6. Income Tax/GST tax shall be deducted as per rule of Government of India/State Government .
7. Rates quoted shall be valid at least for three months from the date of opening of the quotations.
8. University has the right to reject and one or all quotations without assigning any reason

/
Assistant Registrar

Copy To:-

- 1- Registrar, Dr. RML National Law University, Lucnow.
- 2- Finance Officer, Dr. RML National Law University, Lucnow.
- 3- In-charge website with a request to upload it on the website of the University.

Ajit Singh
Assistant Registrar

एल.डी.ए. कानपुर रोड योजना, लखनऊ-226012
L.D.A., Kanpur Road Scheme, Lucknow-226012
दूरभाष सं. 0522-2425902-903 टेलीफैक्स: 0522-2422841
Phone No. 0522-2425902-903, Telefax: 0522-2422841

03-Jun-2022

Name of work -Construction of Dias in Room no. G-19 OF Lecture halls

Bill Of Quantity

S.N.	Reference No.	Description of work	Qty	unit	Rate	Amount
1	DSR-15.15.1	Extra for dismantling trusses, rafters, purlins etc. of wood work for every additional span of one metre or part thereof beyond 10 metres				
		Of sectional area 40 square centimetres and above				
			2.07	cum		
2	DSR-6.2.1	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in				
		Cement mortar 1:4 (1 cement : 4 coarse sand)				
			0.3652	CUM		
3	DSR-13.6.1	20 mm cement plaster of mix 1;6				
			5.47	SQM		
4		supply and filling of local sand in foundation and plinth				
			2.07	CUM		
5	PWD 5.2.2	R.C.C work with cement approved coarse sand and 2 cm .3/4 gauge approved stone grit in the slab proportion 1:2:3 excluding supply of reinforcement and its bending. With 24 b wg binding wire including necessary centering & shuttering & also including supply of all labour tools and plants etc required for proper completion of the works. strength of the concrete shall not be less than m-20				
			1.244	CUM		

neeer
JECE

6		steel reinforcement for rcc work including straighting cutting bending placing in position all complete upto plinth level. 1.244 cum @2%per cum 0.0248cum 7850 kg per cum 195.30 kg	195.3	KG		
7	DSR-11.40	providing and laying rectified glazed ceramic floor antiskid tiles of size 300*300 mm or more of frist quality conforming to IS 15622 of approved make in all colours and shades laid on 20mm thick cement motar 1:4 ,jointing with grey cement slurry @ 3.3kg/sqm including grouting the joint with white cement and matching pigment etc. complete				
			10.37	SQM		
8	DSR 11.41	providing and laying vitrified floor tiles in different sizes with water abosorption less than 0.08% and conforming to IS 15622 of approved make in all colours and shades laid on 20mm thick cement motar 1:4 ,jointing with grey cement slurry @ 3.3kg/sqm including grouting the joint with white cement and matching pigment etc. complete				
			2.73	SQM		
			TOTAL AMOUNT			
			GST@18%			
			NET AMOUNT			

Neeraj
JE (C)