



# डा० राम मनोहर लोहिया राष्ट्रीय विधि विश्वविद्यालय Dr. Ram Manohar Lohiya National Law University

No. 908-22 NLULko/AR/V-1(1)/2019(2309-TC)  
Date: 11 February, 2022

## Quotation Notice

Item wise rates of sealed Quotations are invited for the following work of supply and fixing of aluminium door in Conference Room with an Estimated cost of Rs. 40490.00. B.O.Q. of work as per Annexure-1. The quotations shall be received by speed post and by hand addressed to, "Assistant Registrar (A.S.) RMLNLU Lucknow-226025" in the University up to 3:00P.M. till 18-02-2022.

The quotations are available on the website of the University/main gate of the University only and may be downloaded from rmlnlul.ac.in

### Conditions:-

1. The rates quoted should include the rates for all materials, labour, T&P, cartage, taxes, etc. required for proper completion of work.
2. Work should be carried out as per all edition of C.P.W.D. UPPWD, specificatins.
3. All material required for completion of work shall conform to latest ISI/ C.P.W.D. UPPWD, specificatins.
4. Payment shall be released after completion of work to the satisfaction of Engineer-in-charge.
5. Time of completion shall be 15 Days.
6. Income Tax/GST tax shall be deducted as per rule of Government of India/State Government .
7. Rates quoted shall be valid at least for three months from the date of opening of the quotations.
8. University has the right to reject and one or all quotations without assigning any reason

Assistant Registrar

### Copy To:-

- 1- Registrar, Dr. RML National Law University, Lucnow.
- 2- Finance Officer, Dr. RML National Law University, Lucnow.
- 3- In-charge website with a request to upload it on the website of the University.

Mr. Nagerbra  
AjitaSingh

AjitaSingh  
Assistant Registrar

## BILL OF QUANTITY

S.N	REFERENCE	DESCRIPTION	NOS	L	B	H	QTY	UNIT	RATE	AMOUNT
1	DAR 14.4.1	Making the opening in brick masonry including dismantling in floor or wall and aluminum partition by cutting masonry and making good the damages to walls flooring and jambs complete to match existing surface disposal of malba rubbish to the nearest municipal dumping ground	1	1	1.82		2.59	4.713	sqm	
2	JT PCR	providing and fixing glazing in aluminium door window ventilator shutters and partitions etc with EPDM rubber neoprene gasket etc complete as per the architectural drawings and the direction of engineer in charge with float glass panes of 8mm (weight not less than 20kg/sqm)	1	1	1.82		2.59	4.713	sqm	
3	DAR 21.12.2	providing and fixing aluminium tubular handle bar 32mm outer dia 3mm thick 2100 mm long with ss screws etc complete as per direction of engineer in charge powder coated minimum thickness 50 micron aluminium tubular handle bar					2	nos		
4	DAR 21.13	providing and fixing brass 100mm mortice latch and lock with G LEVERS WITHOUT PAIR of handle					1	nos		
5	20(D)	providing and fixing of floor spring ISI mark heavy quality					2	nos		
6	MR	plaster repairing ,granite work in flooring,pain and putty all complete work including cost material ,labour and disposal of malba.					1	job		
									total amount	
									GST@18%	
									NET AMOUNT	