

डा० राम मनोहर लोहिया राष्ट्रीय विधि विश्वविद्यालय Dr. Ram Manohar Lohiya National Law University

No. No. NLULko/AR/V-01(1)/2019(2309-TC)
Date: September, 2022

Quotation Notice

Item wise rates of sealed Quotations are invited for the following work of water proofing, Aluminium Door Repair, False Ceilling Repair and white washing work, Estimated cost of Rs. 57098/- B.O.Q. of work as per Annexure-1. The quotations shall be received by speed post and by hand addressed to, "Registrar" RMLNLU Lucknow-226012" in the Universityup to 3:00P.M. till 19-09-2022.

The quotation notice are available on the website of the University/main gate of the University only and may be downloaded from rmlnlu.ac.in Conditions:-

1. The rates quoted should include the rates for all materials, labour, T&P, cartage, taxes, etc. required for proper completion of work.

2. Work should be carried out as per all edition of C.P.W.D. UPPWD, specificatins.

3. All material required for completion of work shall confirm to latest ISI/ C.P.W.D. UPPWD, specificatins.

4. Payment shall be released after completion of work to the satisfaction of Engineer-incharge.

5. Time of completion shall be 7 Days.

- 6. Income Tax/GST tax shall be deducted as per rule of Government of India/State Government.
- 7. Rates quoted shall be valid at least for three months from the date of opening of the quotations.
- 8. University has the right to reject and one or all quotations without assigning any reason.
- 9. Tenderer should be mention the quotation Notice number and date along with proprietor's Name, Signature and Date.

(Anil Kumar Mishra) Registrar

Copy To:-

1- Finance Officer, Dr. RML National Law University, Lucnow.

2- In-charge website with a request to upload it on the website of the University.

(Anil Kumar Mishra) Registrar

Annother - 1

Name of work-Putty ,paint, false ceiling,water proofing,alu.door and window repairing work in legal aid room

		Bill of quantity				
S.N.	Referen ce No.	Description of work	Qty	unit	Rate	Amount
1	DSR 14.46	Removing existing oil bound distemper by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete area-(3.04*3.66)4	44.59	Sqm		
2		Providing and applying white cement based putty of average thickness 1mm of approved brand and manufacture over the plastered wall surface even and smooth complete but on oid treated surface.				
	DSR13.80		44.59	Sqm		
3	DSR13.41	Distempering with oil bound washale distemper of approved brand and manufacture to given an even shade: new work (two or more coats) over and including water thinnabl priming coat with cement primer	44.59	Sqm		
4	DAR 12.45	providing and fixing false ceiling at all height includind providing / reparing and fixing of frame work of special sections power pressed from ms sheet and galvanized with zinc coating of 120grm/sqm and consisting of angle cleats of size 25mm center to centre one flange fixed to the ceilling of cleat fixed to the angle hangers of 25*10*.50 mm of required lenth with nuts etc fully perforated gypsum plaster board of size 1200*2400*12.5 mm having approx 15% perforated area with perforation size and pattern as approved by the engineer in charge and as per manufacture specification with all 4 side lapered and backed by acoustical tissue with nrc value not less than 0.60 area- 3.65*3.048				
	21.12.2		11.14	sqm		

	DAR 5 21.12.2	provind and fixing aluminium tubular handle bar 32mm outer dia 3mm thick 2100 mm long with ss srews etc complete as per direction of engineer in charge powder coated minimum thickness 50 micron aluminium tubular handle bar area -(1.85*2.50)3	5.57	sqm		
6	DSR 22.6	providing and laying water proofing treatment on roofs of slabs by appling cement slurry mixed with water proofing cement compound consisting of applying fourt and final layer of brick tiling with cement morter area-6*7=42		sqm		
				TOTAL	VT	
				MET AMOUNT		

neery JECCI