



डा० राम मनोहर लोहिया राष्ट्रीय विधि विश्वविद्यालय Dr. Ram Manohar Lohiya National Law University

No: 489-54 NLULko/Admin/M-51/2020(2459)
Date: 19 April, 2024

Quotation Notice

Item wise rates of sealed Quotations are invited for the following work of window glass and Putti work in Type-3 Estimated cost of Rs. 92,610/- B.O.Q. of work as per Annexure-1. The quotations shall be received by speed post and by hand addressed to, "Joint Registrar RMLNLU Lucknow-226012" in the University up to 3:00P.M. till 25-04-2024.

The quotations are available on the website of the University/main gate of the University only and may be downloaded from rmlnu.ac.in

Conditions:-

1. The rates quoted should include the rates for all materials, labour, T&P, cartage, taxes, etc. required for proper completion of work.
2. Work should be carried out as per all edition of C.P.W.D. UPPWD, specificatins.
3. All material required for completion of work shall conform to latest ISI/ C.P.W.D. UPPWD, specificatins.
4. Payment shall be released after completion of work to the satisfaction of Engineer-in-charge.
5. Time of completion shall be 15 Days.
6. Income Tax/GST tax shall be deducted as per rule of Government of India/State Government .
7. Rates quoted shall be valid at least for three months from the date of opening of the quotations.
8. University has the right to reject and one or all quotations without assigning any reason

Joint Registrar

Copy To:-

1- Main Gate Notice Board.

2- In-charge website with a request to upload it on the website of the University.

Joint Registrar

Name of work - window glass ,glassb putt WORK in type 3 (block A & B)outer side

Bill Of Quantity & Details of measurement

S.N.	Reference No.	Description of work	Qty	unit	Rate	Amount
1	dsr 14.5	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty				
	14.5.1	Float glass panes of nominal thickness 4 mm (weight not less than 10kg/sqm)				
			62.14	sqm		
2	dsr 14.72	providing and fixing double scaffolding system (cup lock type) on the exterior/interior side up to seven story height made with 40mm dia m.s. tube 1.5 m centre to centre horizontal and vertical tubes joining with cup and lock system with m.s. tube m.s. tube challies m.s. clamps and m.s. stair case system in the scaffolding for working platform etc. and maintaining it in a serviceabl condition foe the required duration as approved and removing it thire after. the scaffolding system shall be stiffened with bracings runners connection with the building etc whenever required for inspection of the work men etc. complete as per direction and approval of engineer in charge . the elevational area of the scaffolding shall be measured for payment purpose. the payment will be made once irrespective of duration of scaffolding.				
			70	sqm		
			70	sqm		
			Total amount			
			gst @18%			
			NET AMOUNT			

Sanyal