

डा० राम मनोहर लोहिया राष्ट्रीय विधि विश्वविद्यालय Dr. Ram Manohar Lohiya National Law University

No. 13/1/-22 NLULko/Admin/M-51/2020(2459) Date: 20 August, 2022

Quotation Notice

Item wise rates of sealed Quotations are invited for the following work of Supply and fixing of PVC Door in Type-1, Estimated cost of Rs. 93804/- B.O.Q. of work as per Annexure-1. The quotations shall be received by speed post and by hand addressed to, "Assistant Registrar (A.S.) RMLNLU Lucknow-226012" in the Universityup to 3:00P.M. till 25-08-2022.

The quotations are available on the website of the University/main gate of the University only and may be downloaded from rmlnlu.ac.in

Conditions:-

1. The rates quoted should include the rates for all materials, labour, T&P, cartage, taxes, etc. required for proper completion of work.

2. Work should be carried out as per all edition of C.P.W.D. UPPWD, specificatins.

3. All material required for completion of work shall conform to latest ISI/ C.P.W.D. UPPWD, specificatins.

4. Payment shall be released after completion of work to the satisfaction of Engineer-in-

5. Time of completion shall be 7 Days.

6. Income Tax/GST tax shall be deducted as per rule of Government of India/State

7. Rates quoted shall be valid at least for three months from the date of opening of the

8. University has the right to reject and one or all quotations without assigning any reason

Copy To:-1- Finance Officer, Dr. RML National Law University, Lucnow.

2- In-charge website with a request to upload it on the website of the University.

		Bill Of Quantity & Details of measurement		e 1		
	Referenc	biii Of Quantity & Details of measurement	Ī	T		
.N.	e No.	Description of work	Qty	unit	Rate	Amoun
1	DSR- 9.119	Providing and fixing factory made P.V.C. door frame of size 50x47 mm with awall thickness of 5 mm, made out of extruded 5mm rigid PVCfoam sheet, mitred at corners and joined with 2 Nos of 150 mm long brackets of 15x15 mm M.S. square tube, the vertical door frame profiles to be reinforced with 19x19 mm M.S. square tube of 19 gauge, EPDM rubber gasket weather seal to be provided through out the frame. The door frame to be fixed to the wall using M.S. screws of 65/100 mm size, complete as per manufacturer's specification and direction of Engineer- in-Charge.				
			58.44	m		
2		Providing and fixing factory made panel PVC door shutter consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19 mm x 19 mm for styles and 15x15 mm for top & bottom rails. M.S. frame shall have a coat of steel primers of approved make and manufacture. M.S. frame covered with 5 mm thick heat moulded PVC 'C' channel of size 30 mm thickness, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on both side forming styles and 5 mm thick, 95 mm wide PVC sheet out of which 75mm shall be flat and 20 mm shall be tapered in 45 degree on the inner side to form top and bottom rail and 115 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided both side of the panel. 10 mm (5 mm x 2) thick, 20 mm wide cross PVC sheet be provided as gap insert for top rail & bottom rail, paneling of 5 mm thick both side PVC sheet to be fitted in the M.S. frame welded/ sealed to the styles & rails with 7 mm (5 mm+2 mm) thick x 15 mm wide PVC sheet beading on inner side, and joined together with solvent cement adhesive. An additional 5 mm thick PVC strip of 20 mm width is to be stuck on the interior side of the 'C' Channel using PVC solvent adhesive etc. complete as per direction of Engineer-in-charge, manufacturer's specification & drawing.	15.33	sam		
		30 mm thick plain P VC door shutters	15.55	sqiii		
	DAR	Fixing chowkhats in existing opening inluding embedding chowkhats in floors or walls cutting masonry for holdfasts embedding hold fasts in cement concrete blocks of size 15*10*10 cm with cement concrete 1;3;6 painting two coats of approved wood preservative to side of chowkhats and making good the damages to walls and floors as required complete. Door chowkhats				
			12	job		
				G	T@18%	
				5.		

